

GOVERNMENT OF INDIA  
MINISTRY OF ROAD TRANSPORT AND HIGHWAYS

## **TENDER DOCUMENT**

Construction of 4-Lane National Highway  
NH-48 Section: Km 120.000 to Km 185.000  
(Under Bharatmala Pariyojana Phase-II)

Tender Reference: MORTH/NH48/2025/BMP-II/0847  
Estimated Cost: INR 1,245.67 Crore  
Bid Submission Deadline: 15th March 2025

## **SECTION 1: SCOPE OF WORK**

1.1 The scope of work includes the design, construction, and completion of a 4-lane divided highway with paved shoulders from Km 120.000 to Km 185.000 on National Highway NH-48. The project includes construction of bridges, flyovers, underpasses, service roads, toll plazas, and all associated infrastructure.

1.2 The Contractor shall be responsible for obtaining all necessary environmental clearances from the Ministry of Environment, Forest and Climate Change (MoEFCC) and State Pollution Control Board (SPCB) before commencing construction activities.

1.3 The project traverses through agricultural land, forest areas (approximately 12 hectares of forest diversion required), and semi-urban settlements. The Contractor shall ensure minimal disruption to existing communities and ecosystems.

## **SECTION 2: ENVIRONMENTAL REQUIREMENTS**

2.1 Environmental Impact Assessment: The Contractor shall comply with the EIA Notification 2006 (as amended) and obtain Environmental Clearance (EC) from MoEFCC. An Environmental Management Plan (EMP) shall be submitted within 60 days of contract award.

2.2 Dust Control: During construction, the Contractor shall implement dust suppression measures including water sprinkling at least twice daily on all active construction areas, access roads, and material storage sites. Wind barriers of minimum 3m height shall be erected around all crushing and batching plants.

2.3 Noise Control: Construction activities generating noise levels above 75 dB(A) at the nearest habitation shall be restricted to daytime hours (7:00 AM to 6:00 PM). The Contractor shall maintain noise monitoring records and submit monthly reports.

2.4 Tree Plantation: The Contractor shall plant trees along the highway corridor as per the approved plantation plan. A minimum of 3 trees shall be planted for every tree felled during construction. The survival rate shall be maintained at 80% for a period of 3 years.

2.5 The Contractor should generally follow good environmental practices during construction activities.

## **SECTION 3: WASTE MANAGEMENT**

3.1 Construction and Demolition Waste: The Contractor shall prepare a Construction and Demolition (C&D;) Waste Management Plan in compliance with the C&D; Waste Management Rules, 2016. A minimum of 50% of C&D; waste shall be recycled or reused on-site.

3.2 Hazardous Waste: All hazardous wastes including used oil, bitumen residue, chemical containers, and contaminated soil shall be disposed of through authorized recyclers/treatment facilities as per the Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016.

3.3 The Contractor shall ensure proper waste disposal at the construction site.

## **SECTION 4: MATERIAL SPECIFICATIONS**

4.1 The Contractor shall use BIS-certified materials conforming to relevant Indian Standards. Preference shall be given to locally sourced materials to reduce transportation emissions.

4.2 Fly Ash Utilization: In compliance with the MOEF notification on fly ash utilization, the Contractor shall use fly ash-based products (bricks, cement, embankment fill) wherever technically feasible. A minimum of 25% fly ash shall be blended in cement used for non-structural applications.

4.3 Reclaimed Asphalt Pavement (RAP): Where existing pavement is being removed, the Contractor shall reclaim and recycle a minimum of 30% of the asphalt material for use in new pavement layers.

## **SECTION 5: WATER MANAGEMENT**

5.1 Water Conservation: The Contractor shall implement water conservation measures at all construction camps and batching plants. Recycling of wash water from ready-mix concrete plants is mandatory.

5.2 Stormwater Management: The highway design shall incorporate adequate stormwater drainage systems including cross-drainage structures, roadside drains, and retention ponds at critical locations.

5.3 Ground Water Protection: The Contractor shall not extract groundwater beyond the limits specified in the Central Ground Water Authority (CGWA) No Objection Certificate. Tube well installations require prior CGWA approval.

## **SECTION 6: HEALTH AND SAFETY**

6.1 The Contractor shall comply with all applicable labor laws and safety regulations. Personal Protective Equipment (PPE) shall be provided to all workers at the construction site.

6.2 A Safety Officer shall be appointed full-time at the project site.

## **SECTION 7: QUALITY ASSURANCE**

7.1 The Contractor shall establish a Quality Assurance laboratory at the project site equipped with all testing equipment as per MORTH specifications.

7.2 Third-party quality audits shall be conducted quarterly.

## **SECTION 8: FINANCIAL TERMS**

8.1 The bid shall be evaluated on the basis of the lowest quoted price (L1 system). No additional weightage is given for environmental or sustainability criteria in bid evaluation.

8.2 Performance Bank Guarantee of 5% of contract value shall be submitted.